

ESTIMATED MAXIMUM LOADING FLATBED TRAILERS

OD	Wall	Pieces (DRL)	Feet	LBS	OD	Wall	Pieces (DRL)	Feet	LBS
6.625	0.250	62	266.00	45,429.00	26	0.250	9	360.00	24,775.00
6.625	0.280	56	2,408.00	45,728.00	26	0.375	9	360.00	36,979.00
6.625	0.432	37	1,591.00	45,503.00	26	0.500	8	321.00	43,616.00
8.625	0.250	47	2,021.00	45,230.00	28	0.312	9	360.00	33,246.00
8.625	0.322	37	1,591.00	45,471.00	28	0.375	9	360.00	39,866.00
8.625	0.500	24	1,032.00	44,820.00	28	0.500	7	280.00	41,157.00
10.75	0.250	38	1,634.00	45,850.00	30	0.312	9	360.00	35,647.00
10.75	0.365	26	1,118.00	45,301.00	30	0.375	9	260.00	42,754.00
10.75	0.500	19	817.00	44,763.00	30	0.500	7	280.00	44,150.00
12.75	0.250	32	1,376.00	45,972.00	32	0.375	9	360.00	45,641.00
12.75	0.375	21	903.00	44,798.00	32	0.500	6	240.00	40,409.00
12.75	0.500	16	688.00	45,050.00	34	0.375	8	320.00	43,133.00
14	0.250	29	1,247.00	45,827.00	34	0.500	6	240.00	42,974.00
14	0.375	19	817.00	44,625.00	36	0.375	5	200.00	28,562.00
14	0.500	14	602.00	43,440.00	36	0.500	5	200.00	37,950.00
16	0.250	25	1,075.00	45,247.00	36	0.625	4	160.00	37,816.00
16	0.375	17	731.00	45,790.00	40	0.375	4	160.00	25,416.00
16	0.500	12	559.00	46,313.00	40	0.500	4	160.00	33,781.00
18	0.250	22	946.00	44,878.00	42	0.375	4	160.00	26,698.00
18	0.375	15	645.00	45,569.00	42	0.500	4	160.00	35,491.00
18	0.500	11	473.00	44,244.00	42	0.625	4	160.00	44,230.00
20	0.250	20	860.00	45,370.00	42	0.750	3	120.00	39,686.00
20	0.375	13	559.00	43,977.00	48	0.375	4	160.00	30,547.00
20	0.500	20	430.00	44,819.00	48	0.500	4	160.00	40,622.00
22	0.375	12	516.00	44,732.00	48	0.750	3	120.00	45,460.00
22	0.500	9	387.00	44,474.00	54	0.375	2	80.00	17,197.00
24	0.250	15	645.00	40,938.00	54	0.500	2	80.00	22,876.00



24	0.375	11	473.00	44,798.00	60	0.375	2	80.00	19,122.00
24	0.500	8	344.00	43,210.00					